

*Project:* **State of Nebraska - NSOB 4<sup>th</sup> floor**

**4178**

*Proj. No.*

*Date:* October 31, 2014

*Note:* This addendum is hereby made a part of the contract documents to the same extent as if it were originally included therein. Contract documents shall be considered modified or revised as hereinafter described.

- 
1. Bid date changed from November 6<sup>th</sup> to Wednesday, November 12<sup>th</sup> at 2:00 P.M.
  2. Door Type 1 wood species to be "hardwood".
  3. Door Type 2 wood cut to be "rift cut".
  4. Door Schedule Note 3 - "floor stop to be located by column to eliminate tripping hazard".
  5. Reception desks and west wall features to be centered below gwb cloud.
  6. Provide nominal 5" wide gwb header between east edge of new suspended ceiling system and existing elevator lobby suspended ceiling system nominally 1/2" below suspended ceiling system. Finish gwb P7.
  7. Owner (State) will remove the moveable walls, ceiling-mounted projector, drop-down screen, and whiteboard prior to the start of construction.
  8. Contractor to relocate ceiling-hung directional signage.
  9. Contractor to salvage carpet tile being removed and return to Owner for stock material.
  10. Contractor will be responsible for bagging meters as needed for parking. Typical building hours are 7:30-5:00.
  11. Background checks with the Nebraska State Patrol are not required.
  12. Questions are to be emailed to Dan Mulligan at Innerspace Studios with "NSOB 4 construction" in subject line, dmulligan@innerspace-studios.com.