

# CRAFT STATE OFFICE BUILDING CORNICE REPAIR

## Addendum 1

North Platte, Nebraska  
1605

Wilkins Architecture Design Planning  
2908 West 39<sup>th</sup> Street, Suite A  
Kearney, Nebraska 68845  
308-237-5787

Date Issued: June 1, 2016

Ad. Date: June 6, 2016

TO ALL BID DOCUMENT HOLDERS OF RECORD:

Acknowledge receipt of this addendum by inserting its number in the space provided on the BID FORM. Failure to do so may subject Bidder to disqualification. This Addendum forms a part of the BIDDING DOCUMENTS and modifies them as follows.

-----

**Addendum 1 – 1 Specification Index**

Revise date of Walk-Thru to June 15, 2016 at 1:00 p.m.

**Addendum 1 – 2 Specification Advertisement for Bids**

Revise date of Pre-Bid Walk-Thru to June 15, 2016 at 1:00 p.m.

**Addendum 1 – 3 Sheet ASK-3 Section Details**

On detail 1/ASK-3 ROOF SECTION DETAIL revise note which currently reads:

“EXISTING PAN JOINT STRUCTURE” to read: “EXISTING PAN JOIST, LOCATE AND DO NOT DISTURB EXISTING REINFORCING.”

On detail 1/ASK-3 ROOF SECTION DETAIL revise note which currently reads: “DRILL AND EPOXY #5 INTO EXIST. BRICK w/ 6” EMBED w/ HILTI HY20 ADHESIVE (LOCATE EXIST. PAN JOIST PRIOR TO DRILLING INSTALL REBAR INTO JOIST” to read: “DRILL AND EPOXY #5 INTO EXIST. BRICK w/ 6” EMBED w/ HILTI HY20 ADHESIVE (LOCATE EXIST. PAN JOIST PRIOR TO DRILLING INSTALL REBAR INTO JOIST. CARE SHALL BE TAKEN WITH INSTALLATION OF REINFORCING INTO EXISTING BRICK. REMOVE AND REPLACE ANY DAMAGED BRICK OR NOT SUITABLE”.